



MAHARSHI DAYANAND UNIVERSITY, ROHTAK
NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotations are hereby invited by the undersigned for and on behalf of Registrar, M.D. University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D. B & R, M.E.S. & Central P.W.D. UHBVN/DHBVN or any other State/Central Govt. Department for electrical works on dated 19/04/2024 at 3 PM..... Quotations will be opened at the same date and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DNIQ may be seen on University website or in the office of Sub-Division.

<u>Description</u>	<u>App.Amt.</u>	<u>Earnest Money</u>	<u>Time Limit</u>
"S/E of electrical points in new reading hall on ground floor in Vivekananda Library, in M.D. Rohtak"			32680/-

Conditions: -

1. The work will be carried out strictly in accordance with the PWD Haryana specification and approved DNIQ.
2. Other taxes will be deducted as applicable time to time.


Sub-Divisional Engineer (Elect.)
M.D. University, Rohtak. 



SDE/(Elect.)/2024/ 196-99.....Dated 12-04-2024..

Cope of the above is forwarded to the following for information and necessary action:-

The Executive Engineer, M.D. University, Rohtak

Notice Board

Contractors/Agencies


Sub-Divisional Engineer (Elect.)
M.D. University, Rohtak. 

DNIT for "Supply and erection of Electrical points in New Reading Hall on Ground Floor in Vivekananda Library, in MDU, Rohtak".

Sr. No.	HSR/NS	Description of items	Unit.	Qty.	Rate to be quoted by Agency
1	5.42	Dismantling cement conglomerate / terrazzo floors 25 mm to 50 sqmm manually/ by mechanical means and disposal of material within standard lead as per direction of Engineer- in-charge.	Per Sqm	0.5	
2	23.3.6.2	Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in PVC Conduit etc as required. 1 run of Size 2.50 Sqmm(1.1.80mm)	Mtr	70	
3	23.3.6.7	Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in PVC Conduit etc as required 2 run of Size 2.50 Sqmm(1.1.80mm)	Mtr	12	
4	23.7.6.1	Supply and erection of PVC CONDUIT ISI marked (Medium) recessed in wall/ceiling etc. including the cost of PVC bends, inspection boxes, iron hooks and cement concrete etc. complete in all respect up to the entire satisfaction of Engineer-in-Charge of work. PVC pipe of 20 mm dia.	Mtr	55	
5	23.8.11.1	Providing and fixing modular type accessories of approved make in existing box including fixing and making necessary connections, complete in all respect. 5 amp 1 way switch	Each	60	
6	23.8.11.4	Providing and fixing modular type accessories of approved make in existing box including fixing and making necessary connections, complete in all respect. 5 amp Socket	Each	90	
7	23.22.5.1	Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 6 amp. to 32 amp Single Pole	Each	4	
8	NS	Supply and erection of inner and outer face plate in existing trunk U- PVC Trunking/Channel 8 Modules Make- Anchor Rider or Equivalent	Each	30	