


MAHARSHI DAYANAND UNIVERSITY, ROHTAK
NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotations are hereby invited by the undersigned for and on behalf of Registrar, M.D. University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D. B & R, M.E.S. & Central P.W.D. UHBVN/DHBVN or any other State/Central Govt. Department for electrical works on dated 26/3/2024 at 3 PM. Quotations will be opened at the same date and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DNIQ may be seen on University website or in the office of Sub-Division.

Description	App.Amt.	Earnest Money	Time Limit
"P/F of wiring for light point at lawn in VC Residence in MDU, Rohtak".			16100/-

Conditions: -

1. The work will be carried out strictly in accordance with the PWD Haryana specification and approved DNIQ.
2. Other taxes will be deducted as applicable time to time.


Sub-Divisional Engineer (Elect.)
M.D. University, Rohtak. *h*


SDE/(Elect.)/2024/ 134-36 Dated 18/3/2024

Cope of the above is forwarded to the following for information and necessary action:-

The Executive Engineer, M.D. University, Rohtak

Notice Board

Contractors/Agencies


Sub-Divisional Engineer (Elect.)
M.D. University, Rohtak. *h*

DNIT for "wiring for Light Point at Lawn in VC Residence in MDU Rohtak

Sr. No.	HSR/ NS	Description	Qty.	Unit	Rate to be quoted by Agency
1	23.5.6.2	Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in existing MS/PVC Conduit etc as required. 1 run of Size 2.50 Sqmm(1.1.80mm)	70	Meter	
2	23.5.6.7	Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in existing MS/PVC Conduit etc as required. 2 run of Size 2.50 Sqmm(1.1.80mm)	14	Meter	
3	23.6.6.4	Supply and erection of MS conduit pipe 1.6 mm thick , ISi marked surface/ recessed inslab/ wall/ ceiling etc. including cost of MS bends, inspection box and all other material required to complete the job in all respect up to the entire satisfaction of Engineer-in-Charge of work.MS pipe of 40 mm dia.	2	Meter	
4	23.7.6.2	Supply and erection of PVC CONDUIT ISi marked (Medium) recessed in walVceiling etc. including the cost of PVC bends, inspection boxes, iron hooks and cement concrete etc. complete in all respect up to the entire satisfaction of Engineer-in-Charge of work. PVC pipe of 25 mm dia.	45	Meter	
5	23.8.10.1	Providing and fixing GI concealed sheet metal boxes with inner and outer face plate including concealing the box in wall and fixing in position with inner plate and face plate with all labour and material required for the job complete in all respects.1 & 2 Modules including combined plate for Telephone and data	1	Each	
6	623.22.5.1	Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 6 amp. to 32 amp Single Pole	2	Each	
7	N S	Supply of 30 watt LED Lamp post complete as per entire satisfaction of the Engineer-in-charge.	2	Each	