

Ucc-10316
13/11/24

MAHARSHI DAYANAND UNIVERSITY, ROHTAK NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotation are hereby invited by the undersigned for and on behalf of Registrar, M.D University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D.B & R. M.E.S & Central P.W.D. Or any other State/ Central. Govt. Department on date 19/11/2024 at 03:00 PM for societies and on dated 20/11/2024 at 03:00 PM the both contractors & societies quotations will be opened at the same date and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DINQ may be seen on University website or in the office of Sub-Division.

Sr. No.	Description	App. Amount	Time limit
1.	Supply of PH Items for Wrestling hall, Boxing hall and Gymnasium in sports complex in MDU, Rohtak.	Rs.11760	05 Days
2.	P&F aluminum partition in lab no.120 in CBT building in MDU, Rohtak.	Rs.23200	10 Days
3.	Supply of civil item for IMSAR building in MDU, Rohtak.	Rs.9800	05 Days
4.	Supply of PH Items for Department of Zoology in MDU, Rohtak.	Rs.9600	05 Days
5.	P&F steel stands for flower pots in lab no.220 in CBT building in MDU, Rohtak.	Rs.22200	10 Days
6.	Distemping and Painting and PVC wall paneling in University outreach cell at 1 st floor in Health Centre in MDU, Rohtak.	Rs.22400	10 Days
7.	Special repair of overhead water tank for fire safety on terrace in library building in MDU, Rohtak.	Rs.49400	15 Days

Conditions:-


1. The work will be carried out strictly in accordance with the PWD Haryana Specification and approved DINQ.
2. Other taxes will be deducted as applicable from time to time.

Sub -Divisional Engineer (C-II)
M.D. University, Rohtak.

SDE(C-II)/2024/.....797-801.....Dated...11/11/24.....

Cope of the above is forwarded to the following information and necessary action:-

1. The Executive Engineer/C-I, M.D. University, Rohtak.
2. The Executive Engineer /C-II M.D. University, Rohtak.
3. Notice Board
4. Directed , UCC for Uploading it on University web site
5. Contractors / Agencies.


13/11


11/11/24

Sub -Divisional Engineer (C-II)
M.D. University, Rohtak

DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Supply of PH Items for Wrestling hall, Boxing hall and Gymnasium in sports complex in MDU, Rohtak.


App. Amount Rs: - 11760 /-

Time Limit: 05 Days

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	N.S.	C.I Tap ½" dia	03	Nos.		
2.	N.S.	CP knob	24	Nos.		
3.	N.S.	PVC cistern handle	06	Nos.		
4.	N.S.	CP connection 24"x ½" dia	06	Nos.		
5.	N.S.	Brass spendal heavy	06	Nos.		
6.	N.S.	PVC waste jail 1½" dia for washroom and urinal	04	Nos.		
7.	N.S.	PVC waste pipe 32 mm dia	06	Nos.		
8.	N.S.	PVC ball cock (LDC) long	06	Nos.		
9.	N.S.	White seat cover (Victrex)	02	Nos.		
10.	N.S.	M. Seal	250	Gram		
11.	N.S.	PVC syphene washer ½" dia	01	Pkt.		
12.	N.S.	PVC syphene washer ¾" dia	01	Pkt.		
13.	N.S.	Jet pipe set	02	Nos.		
14.	N.S.	Safeda	200	Gram		
15.	N.S.	Dhaga	01	Pkt.		

Note:-

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.


11/11/25

DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - P&F aluminum partition in lab no.120 in CBT building in MDU, Rohtak.

App. Amount Rs: - 23200 /-

Time Limit: 10 Days

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	12.157.1.1	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	36.94	Kg		
2.	12.157.1.1 (LR only)	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	39.44	Kg		
3.	12.158.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board Pre-laminated particle board with decorative lamination on both sides	3.10	Sqm		

Note:-

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.


21/11/24

DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Supply of civil item for IMSAR building in MDU, Rohtak.

App. Amount Rs: - 9800 /-

Time Limit: 05 Days

Sr. No.	H.S.R : / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	N.S.	18 mm MDF board both side laminates action tesa make Size 8' x 4'	03	Nos.		
2.	N.S.	SS self screw 1½"	250	Nos.		

Note:-

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.


11/11/24

DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Supply of PH Items for Department of Zoology in MDU, Rohtak.

App. Amount Rs: - 9600 /-

Time Limit: 05 Days

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	N.S.	PVC pipe (Supreme) 2" dia	80	Rft.		
2.	N.S.	PVC elbow (Supreme) 2" dia	15	Nos.		
3.	N.S.	PVC Tee (Supreme) 2" dia	16	Nos.		
4.	N.S.	PVC solution	200	Gram		
5.	N.S.	Brass spendal dish heavy	06	Nos.		
6.	N.S.	PVC waste pipe 32 mm dia	10	Nos.		
7.	N.S.	PVC waste jali 32 mm dia	10	Nos.		
8.	N.S.	CP pillar cock (Kunex) 1/2" dia	02	Nos.		
9.	N.S.	PVC cistern handel for (L.D.C)	06	Nos.		
10.	N.S.	PVC connection pipe 24" x 1/2"	06	Nos.		
11.	N.S.	PVC ball cock for (L.D.C) long	06	Nos.		
12.	N.S.	M. Seal	250	Gram		
13.	N.S.	White cement	02	Kg		

Note:-

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.


11/11/24

DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - P&F steel stands for flower pots in lab no.220 in CBT building in MDU, Rohtak.

App. Amount Rs: - 22200 /-

Time Limit: 10 Days

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	13.29.2	Steel work in built section in framing as per site requirement	131.87	kg		
2.	13.18	P/F hard drawn steel wire 75x25 mm dia	8.02	Sqm		
3.	11.82.1	Painting the wooden / metal surface with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	12.4	Sqm		

Note:-

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

Am
17/11/24

DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Distempering and Painting and PVC wall paneling in University outreach cell at 1st floor in Health Centre in MDU, Rohtak.

App. Amount Rs: - 23400 /-

Time Limit: 10 Days

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	30.34.1	Distempering with 1 st quality distemper	426.5	Sqm		
2.	30.16.2	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape	06.00	Sqm		
3.	11.58	Providing and applying two coats white cement based putty	06.00	Sqm		
4.	11.65.1	Distempering with 1st quality acrylic distemper Two or more coats on new work	06.00	Sqm		
5.	N.S.	Providing and fixing PVC wall paneling of heavy duty including all fitting and fixtures complete as per entire satisfaction of engineer in charge.	168.00	Sqft.		

Note:-

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.


12/11/24

DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Special repair of overhead water tank for fire safety on terrace in library building in MDU, Rohtak.

App. Amount Rs: - 49400 /-

Time Limit: 15 Days

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	5.25	Demolishing R.C.C. work manually/ by mechanical means cum including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - incharge.	2.3	Cum		
2.	5.45	Dismantling of old plaster and skirting complete	36.00	Sqm		
3.	28.15	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement sluny mixed with water proofing cement compound consisting of applying (a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound@ 0.253 kg/ sqm This layer will be allowed to air cure for 4 hours. (b) Second layer of sluny of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours.	30.02	Sqm		

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
4.	10.59	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622; of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1 :4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	13.00	Sqm		
5.	10.58	P/F 1 st quality ceramic glazed wall size complete	17.03	Sqm		
6.	11.9.1	15 mm cement plaster on rough side of single or half brick wall of mix: 1 :4 (1 cement: 4 coarse sand)	21.80	Sqm		
7.	13.30.1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	129.87	Kg		
8.	22.94.6	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 50 mm nominal bor	01.00	Nos.		
9.	22.98.5	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 50 mm nominal bor	01.00	Nos.		
10.	22.88.6	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 50 mm dia nominal bore	03.00	Mtr.		

Sr. No.	H.S.R / Ref. No.	Description	Qty.	Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
11.	3.1.18	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead up to 10 km for all lifts, complete as per directions of Engineer-in-charge.	04.00	Cum		
12.	9.32	Providing & fixing UV stabilised fibreglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigis incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.	16.00	Sqm		
13.	N.S.	P/F GI Tee 50mm complete as per entire satisfaction of engineer in charge	01.00	Nos.		

Note:-

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

Chauhan
24/11/24