

MAHARSHI DAYANAND UNIVERSITY, ROHTAK

NOTICE INVITING QUOTATIONS

Scaled percentage/item rate quotations are hereby invited by the undersigned for and on behalf of Registrar, M.D. University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D. B & R, M.E.S. Central P.W.D. UHBVN/DHBVN or any other State/Central Govt. Department for electric works on dated 19/11/2025 at 3 PM. Quotations will be opened at the same date and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DNIQ may be seen on University website or the office of Sub-Division.

Description	App.Amt.	Earnest Money	Time Limit
"Copper wiring of officer Residence No-3, in MDU, Rohtak".		49825/-	15 Days

Conditions: -

1. The work will be carried out strictly in accordance with the PWD Haryana specification and approved DNIQ.
2. Other taxes will be deducted as applicable time to time.

Sub-Divisional Engineer (Elect)

o/c M.D. University, Rohtak

SDE/(Elect.)/2025/ 1252-60 Dated 12/11/2025

Cope of the above is forwarded to the following for information and necessary action:-

The Executive Engineer C-II, M.D. University, Rohtak

Notice Board

Contractors/Agencies

Sub-Divisional Engineer (Elect.)

o/c M.D. University, Rohtak

DNIT for "Copper wiring for Officer Residence No. 3 in MDU, Rohtak. (E.I)

Sr. No.	Description of items	Qty.	Unit.	Rate to be quoted by Agency
1	24.13.19 Supply and Erection of 16 Sq mm 2 core (UnArm.)	53	Mtr	
2	Supply and erection of Modular case circuit breaker single pole/4 pole on existing wall/pedestal/Panel including bounding to earth and making necessary connections required to complete the job in all respect up to the entire satisfaction of the Engineer-in-charge of the work. 23.22.1.3 TRIPLE POLE MCCB 16 to 100 Amp, 25 KA	1	Nos	
3	Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 23.22.5 6 amp. to 32 amp Single Pole	27	Nos	
4	Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 23.22.5.8 40 amp to 63 amp. MCB's FOUR POLE	1	Nos	
5	Providing and fixing Piano type accessories of approved make in existing box and Bakelite sheet including fixing and making necessary connections, complete in all respect. 23.8.1.6 Call bell 220/230 volts musical type	1	Nos	
6	Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in existing MS/PVC Conduit etc as required. 23.5.6.3 1 run of Size 4 Sqmm(1/2.24mm)	80	Mtr	
7	Supply and erection of PVC CONDUIT ISI marked (Medium) recessed in wal/Vceiling etc. including the cost of PVC bends, inspection boxes, iron hooks and cement concrete etc. complete in all respect up to the entire satisfaction of Engineer-in-Charge of work. 23.7.6.2 PVC pipe of 25 mm dia	82	Mtr	
8	Supply and Fixing Bakelite sheet on existing MS/GI/wooden/PVC box etc including fixing with brass screws and washers. 23.8.1.4 6 pin 15 multi socket on existing sheet	6	Nos	
9	Supply and Fixing Bakelite sheet on existing MS/GI/wooden/PVC box etc including fixing with brass screws and washers. 23.8.2.1 5 mm thick	6	Sqcm	
10	Wiring only in 1.5 sqmm PVC insulated copper conductor cable for LIGHT/FAN/Call bell point in existing conduit pipe and MS boxes including cost of Bakelite cover for MS box, switch, wall socket, ceiling rose/connector etc .23.5.1.3 Group C	17	Each	
11	Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in PVC Conduit etc as required. 23.3.6.1 1 run of Size 1.50 Sqmm(1/1.40mm)	40	mtr	
12	24.4.5 Supply and erection of Single Phase weather proof M.S. box of size 20 cm x 15 cm x 10 cm with hinged cover made of 2 mm thick MS sheet, locking arrangements, housed in wall/fixed on pole , including the cost of 1 no 4 way 16 A Bakelite connector, 1 no. 6 amp SP MCB and 1 Nos. 16 amp. neutral links fixed on Bakelite sheet in the M.S. box including painting and necessary connections	4	Each	
13	EL133 SPN enclosure	7	Each	
14	MCCB Enclosure made of Sheet Steel suitable for mounting MCCB of following ratings 23.22.2.1 MCCB up to 125 A FP	1	Nos	
15	Credit of old material			