

UCC-9533
19/7/24

MAHARSHI DAYANAND UNIVERSITY, ROHTAK


NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotation are hereby invited by the undersigned for and on behalf of Registrar, M.D University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D.(B&R). M.E.S & Central P.W.D. or any other State/ Central. Govt. Department on dated 24/07/2024 at 3.00pm for societies only and on dated 25/07/2024 at 3.00 pm for both contractors & societies. Quotations will be opened at the same date and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DINQ may be seen on University website or in the office of Sub-Division.

Description	App.Amt.
1.) P/F of G.I Water Pipe Line behind Mount Abu Boys Hostel in M.D.U, Rohtak	Rs. 36897/-


Conditions:-

1. The work will be carried out strictly in accordance with the PWD Haryana Specification And approved DINQ.
2. Other taxes will be deducted as applicable time to time.


19/7/24
Sub-Divisional Engineer (PH)
M.D. University, Rohtak.

SDE/(PH.)2024/260-264 Dated 19/07/24
Cope of the above is forwarded to the following for information and necessary action:-

1. The Executive Engineer/C-I, M.D. University, Rohtak.
2. The Executive Engineer /C-II M.D. University, Rohtak.
3. Notice Board
- ✓ 4. Director, UCC for uploading it on University web site
5. Contractors/Agencies


19/7

CO

DETAILED NOTICE INVITING QUOTATIONS

Name of the work:- P/F of G.I Water Pipe Line behind Mount Abu Boys Hostel in M.D.U, Rohtak

App. Amount 36897/-

Time Limit: 05 Days

S. No	H.S.R Ref/No	Description	Qty.	Unit	Rate to be quoted by the bidder
1.	22.91.6	P/F G.I Pipe complete with G.I fittings including trenching up to 0.30 m to 1.00 m depth & refilling etc. 50 mm dia. Nominal bore	23.0	Mtr.	
2	22.94.6	P/F G.I Union in G.I Pipe including cutting & threading the pipe & making long screw etc . complete (new work) 50 mm dia. Nominal bore	2.0	Nos.	
3	22.93.6	Provide & Filling sand envelope of grading zone grade, 100 mm all- round the G.I 50 mm diameter pipe	21.0	Mtr.	
4	21.84.2	Constructing brick masonry inspection chamber sizes as given below up to 0.60 mtr. Average depth in cement mortar 1:5 lime concrete with 40 percent lime mortar 2:3 in foundation cement concrete 1:2:4 benching 12 mm thick cement plaster 1:2	1.0	Nos.	
5	21.85.2	Extra for every 0.30 metre depth of inspection chamber Size 450 mm x 600 mm inside	1.0	0.3 m	
6	NS	Excavation by JCB Machine including refilling the same complete as per entire satisfaction of engineer in charge	5.0	Hs.	
7	NS	P/F G.I Bends in G.I Pipe including cutting & threading the pipe & make long screw etc. complete (new work) 50 mm Nominal bore	4.0	Nos.	
8	NS	Dewatering of pit excavated for repair/connection of pipe line complete	2.0	Job	

In case of any difference in the unit & nomenclature of any of the HRS items of civil, PII work depicted in this DNIT and that given in HRS, the unit and nomenclature given in HSR shall be applicable


19/12/21