

UCC-1014  
9/5/25

**MAHARSHI DAYANAND UNIVERSITY, ROHTAK**  
**NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotation are hereby invited by the undersigned for and on behalf of Registrar, M.D. University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D.B & R.M.E.S & Central P.W.D. Or any other State/ Central. Govt. Department on date **15/05/2025** at 03:00 PM for societies and on dated **16/05/2025** at 03:00 PM the both contractors & societies quotations will be opened at the same date and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DINQ may be seen on University website or in the office of Sub-Division.

Sr. No.	Description	App. Amount	Time limit
1.	Replacement of car shed sheet and extention of shed in Type-IIA /11 in MDU, Rohtak	Rs.18910	07 Days
2.	Raising of back court yard wall and repair of floor in back court yard in Type-I/25 in MDU, Rohtak	Rs.16500	07 Days
3.	Repair of roof and fixing brick broken floor and wall tile in H.No. 28, Type-II in MDU, Rohtak	Rs.30000	07 Days
4.	P/F wall & floor tiles, granite stone in toilet & kitchen in H.No. 11 Type-III duplex in MDU, Rohtak	Rs.20000	07 Days
5.	Distempering & painting and other allied works in Type-II/88, IA/107 in MDU, Rohtak	Rs.41000	07 Days

**Conditions:-**

1. The work will be carried out strictly in accordance with the PWD Haryana Specification and approved DINQ.
2. Other taxes will be deducted as applicable from time to time.

-SD-

Sub-Divisional Engineer (C-I)  
M.D. University, Rohtak.

SDE/(C-I)/2025/.....141-149.....Dated.....9/5/25.....

Cope of the above is forwarded to the following information and necessary action:-

1. The Executive Engineer/C-I, M.D. University, Rohtak.
2. The Executive Engineer/C-II, M.D. University, Rohtak.
3. Notice Board
- ✓ 4. Directed , UCC for Uploading it on University web site
5. Contractors / Agencies.

G.S.

09/5

10

Sub-Divisional Engineer (C-I)  
M.D. University, Rohtak

## **DETAILED NOTICE INVITING QUOTATIONS**

**Name of the work:** - Replacement of car shed sheet and extension of shed in Type-IIA /11  
in MDU, Rohtak

**Time Limit: 07 Days**

<b>Sr. No.</b>	<b>H.S.R/ Ref.No</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any</b>
1.	5.15.1	Removing GI sheet	11.15	Sqm	
2.	13.30.1	Steel work in built up tubular	15.15	Kg	
3.	13.28	Structural steel work in built up sections	56.50	Kg	
4.	9.33	P/F Pre coated iron Profile sheets	18.50	sqm	
5.	N.s.	P/F M.S. fastners 100 x 10 mm including drillings	7	Nos.	

**Note:** - In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.



## **DETAILED NOTICE INVITING QUOTATIONS**

**Name of the work:** - Raising of back court yard wall and repair of floor in back court yard  
in Type-I/25 in MDU, Rohtak

**Time Limit: 07 Days**

<b>Sr. No.</b>	<b>H.S.R/ Ref.No</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any</b>
1.	7.21.1	Brick work in cement mortar 1:4	1.13	Cum	
2.	11.6.1	15 mm cement plaster 1:4	13.62	Sqm	
3.	10.100.1	Cement concrete 1:8:16 with 40mm b/ballast	2.21	Sqm	
4.	10.8	40mm th. Topping C.floor 1:2:4	21.83	Sqm	
5.	10.14	P/F flooring coat 1.30mm	21.83	sqm	

**Note:** - In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.



## **DETAILED NOTICE INVITING QUOTATIONS**

**Name of the work:** - Repair of roof and fixing brick broken floor and wall tile in H.No. 28,  
Type-II in MDU, Rohtak

**Time Limit: 07 Days**

<b>Sr. No.</b>	<b>H.S.R/ Ref.No</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any</b>
1.	30.9	Regarding terracing of mud	49.37	Sqm	
2.	11.26.1	Flush pointing on brick tile	49.37	Sqm	
3.	9.17.1	Providing gola CC 1:2:4	35	mtr	
4.	N.S.	Supply of new brick tile	864	Nos.	
5.	10.63.2	P/F floor tile in cm 1:3	0.74	Sqm	
6.	10.58	P/F 1 <sup>st</sup> quality ceramic glazed wall tiles	1.11	sqm	

**Note:** - In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.



## **DETAILED NOTICE INVITING QUOTATIONS**

**Name of the work:** - P/F wall & floor tiles, granite stone in toilet & kitchen in H.No. 11  
Type-III duplex in MDU, Rohtak

**Time Limit: 07 Days**

<b>Sr. No.</b>	<b>H.S.R/ Ref.No</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any</b>
1.	10.50.1	P/F granite stone,	2.04	Sqm	
2.	5.42	D/m cong/ terrazzo floor	9.97	Sqm	
3.	10.58	P/F ceramic wall tiles	12.87	Sqm	
4.	10.57	P/F Floor tiles 300*300mm	6.47	Sqm	

**Note:** - In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.



## **DETAILED NOTICE INVITING QUOTATIONS**

**Name of the work: - Distempering & painting and other allied works in Type-II/88, 1A/107  
in MDU, Rohtak**

**Time Limit: 07 Days**

<b>Sr. No.</b>	<b>H.S.R/ Ref.No</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any</b>
1.	5.45	Dismantling old plaster	7.75	Sqm	
2.	11.6.1	15mm th c. plaster in cm 1:4	7.75	Sqm	
3.	11.58	P/A Two coat of wall putty	97.84	Sqm	
4.	30.34.1	P/A one coat of OBD	633.20	Sqm	
5.	12.37.2	P/F solide flush door 30mm thick	1.21	Sqm	
6.	12.37.3	P/F solid flush door 25mm th	2.79	Sqm	
7.	11.76	Preparatio of plywood surface	9.59	Sqm	
8.	11.77+11.78	Painting two coat with primer	9.59	Sqm	
9.	30.28.1	P/A one coat of S/E paint	232.92	Sqm	
10.	10.58	P/F wall tile as per Req. Size	0.74	Sqm	
11.	22.108.1	P/F angle valve	1	Nos.	
12.	N.S.	P/F CP shower with revolving joint	1	Nos.	

**Note: -** In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

