

DNIT for Electrical wiring work in garage to be converted in room in H. No. 21/9 J, in MDU, Rohtak"

Sr. No.	H.S.R/ Ref. No.	Description	Qty.	Unit.	Rate to be quoted by agency
1	23.4.1.1	COPPER WIRING WITH MODULAR SWITCHES IN PVC CONDUIT Light/ Fan/ Call bell point with modular type switch/socket and GI box, Modular type plate etc in 1.5 sqmm FRLS PVC insulated copper conductor cable in 1.6 mm thick PVC Conduit pipe. Group - A	12	Each	
2	23.4.4.1	Wiring in PVC system for 3 pin 5 amp. Plug point by using 2 no 1.5 sqmm FRLS copper wire and 1 no 1.5 Sqmm FRLS copper wire , Including providing 1 no 5/6 Amp 3/5 pin Modular type socket and 1 no 5/6 Amp Modular type switch required GI Box, modular face plate etc complete as required Group - A	8	Each	
3	23.4.5.1	Wiring in PVC system for 3 pin 15 amp. Plug point by using 2 no 4 sqmm FRLS copper wire and 1 no 4 sqmm FRLS copper wire for earthing , including providing 1 no 15/16 Amp 3/6 pin Modular socket and 1 no 15/16 Amp Modular switch required GI Box, modular face plate etc complete as required Group -A	4	Each	
4	23.5.6.1	Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in existing MS/PVC Conduit etc as required. 1 run of Size 1.50 Sqmm(1/1.40mm)	36	Mtr.	
5	23.5.6.2	1 run of size 2.50 sqmm (1.180mm)	53	Mtr.	
6	23.5.6.3	1 run of size 4 sqmm (1/2.24 mm)	30	Mtr.	
7	23.7.6.2	Supply and erection of PVC CONDUIT ISI marked (Medium) recessed in walVceiling etc. including the cost of PVC bends, inspection boxes , iron hooks and concrete etc. complete in all respect up to the entire satisfaction of Engineer- in-Charge PVC pipe of 25 mm dia.	39	Mtr.	
8	23.8.11.7	Providing and fixing modular type accessories of approved make in existing box including fixing and making necessary connections, complete in all respect. Step type Fan Regulator 2 modules 300 watt	1	Each	
7	23.22.5.1	Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 6 amp. To 32 amp. Single Pole	7	Nos.	


MAHARSHI DAYANAND UNIVERSITY, ROHTAK
NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotations are hereby invited by the undersigned for and on behalf of Registrar, M.D. University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/Societies registered with Haryana P.W.D. B & R, M.E.S., Central P.W.D., UHBVN/DHBVN or any other State/Central Govt. Department for electrical works on dated 06/04/2026 at 3.00 P.M. Quotations will be opened at the same date and time in the presence of quotationers or representative who like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DNIQ may be seen on University website or in the office of Sub-Division.

Description	App. Amt	Earnest Money	Time Limit
Electrical wiring work in garage to be converted in room in H.No-21/95, In M.D.U Rohtak		33451/-	10 Days

Conditions:


1. The work will be carried out strictly in accordance with the PWD Haryana specification as approved DNIQ.
2. Other taxes will be deducted as applicable time to time.


Sub-Divisional Engineer (Elect.)
M.D. University, Rohtak

SDE/(Elect.)/2026/ 163-165 Dated: 27/03/2026

Copy of the above is forwarded to the following for information and necessary action:-

The Executive Engineer C-I, M.D. University, Rohtak
Notice Board
Contractors/Agencies


Sub-Divisional Engineer (Elect.)
M.D. University, Rohtak