

Ucc-935  
30/4/26

MAHARSHI DAYANAND UNIVERSITY, ROHTAK  
NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotation are hereby invited by the undersigned for and on behalf of Registrar, M.D University, Rohtak for the below noted work from the suppliers/Agencies/Contractors/societies registered with Haryana P.W.D.B & R.M.E.S & Central P.W.D. Or any other State/ Central. Govt. Department on date 06/05/2026 at 03:00 PM for societies and on dated 07/05/2026 at 03:00 PM the both contractors & societies quotations will be opened at the same date and time in the presence of quotationers or representative who may like to be present at that time. However, preference will be given to societies first, if two or more societies participated and found eligible. DINQ may be seen on University website or in the office of Sub-Division.

Sr. No.	Name of Work's	App. Amount	Time limit
1.	Providing and fixing floor tiles and distemper & painting in Office of SDE (Electrical) in Engineering Cell, MDU, Rohtak.	Rs.23,100/-	15 Days
2.	Repair of seating benches in lawn of Vivekananda Library in MDU, Rohtak.	Rs.44,500/-	15 Days
3.	Misc. work at Gate No.04, Public Administration, Gymnasium, B.C.A, UIET and Law Department in MDU, Rohtak.	Rs.38,000/-	15 Days
4.	Providing and fixing vitrified floor tiles in Lab No.213 UIET (E.E) in MDU, Rohtak.	Rs.12,500/-	15 Days
5.	Supply of P.H items for Department of Pharmacy (New Building) in MDU, Rohtak.	Rs.28,034/-	07 Days

Conditions:-

1. The work will be carried out strictly in accordance with the PWD Haryana Specification and approved DINQ.
2. Other taxes will be deducted as applicable from time to time.

- Sd -  
Sub -Divisional Engineer (C-II)  
M.D. University, Rohtak.

Des./SDE/(C-II)/2026/...152-155.....Dated...29/04/2026.....

Copy of the above is forwarded to the following information and necessary action:-

1. The Executive Engineer/C-I, M.D. University, Rohtak.
2. Notice Board
3. Directed, UCC for Uploading it on University web site
4. Contractors / Agencies.

CO

30/4/26

Sub -Divisional Engineer (C-II)  
M.D. University, Rohtak

## DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Providing and fixing floor tiles and distemper & painting in Office of SDE (Electrical) in Engineering Cell, MDU, Rohtak.

App. Amount: - 23,100/-

Time Limit: 15 Days

Sr. No.	H.S.R / Ref. No	Description	Qty. / Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	10.71.2	Providing and laying Vitrified tiles in floor of Size: - 600x600 mm with adhesive complete.	12.21 Sqm		
2.	10.67.2	P/L vitrified tiles of size: - 600*600 mm in skirting complete.	1.41 Sqm		
3.	10.70	Extra for grouting the joints of floor tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade. Complete as per direction of Engineer-in-charge.	13.62 Sqm		
4.	11.65.1	Distemping with OBD two or more coats complete.	48.57 Sqm		
5.	11.58	Providing and applying two coats white cement based putty	36.67 Sqm		
6.	30.28.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One coat	14.18 Sqm		
7.	30.22	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	36.67 Sqm		

**Note:-**

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

*[Signature]*  
29/11/20

## DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Repair of seating benches in lawn of Vivekananda Library in MDU, Rohtak.

App. Amount: - 44,500/-

Time Limit: 15 Days

Sr. No.	H.S.R / Ref. No	Description	Qty. / Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	31.2.1	Chipping of unsound/weak concrete material from slabs, beams, columns etc., 75mm average thickness	28.02 Sqm		
2.	31.1	Providing and fixing hard drawn steel wire fabric of size 75 x25 mm mesh or other suitable size wire mesh to be fixed & firmly anchored to the concrete surface by means of "L" shaped mild steel shear key welded with existing reinforcement including the cost of materials, labour, tool & plants as approved by Engineerin-charge.	23.20 Sqm		
3.	6.30.4	Centering and shuttering including strutting, propping etc. and removal of form for Shelves (Cast in situ)	21.02 Sqm		
4.	31.5.2	Providing, mixing and applying SBR polymer, 75mm thick in Grade M 25 with cement content not less than 330 kg per cum	28.02 Sqm		
5.	11.6.1	15 mm cement plaster on the rough side of single or half brick wall of mix : 1 :4 (1 cement: 4 fine sand)	18.03 Sqm		
6.	10.58	Providing and fixing 1st quality ceramic glazed wall tiles complete.	2.60 Sqm		

**Note:-**

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

*ML*  
29/4/28

## DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Misc. work at Gate No.04, Public Administration, Gymnasium, B.C.A, UIET and Law Department in MDU, Rohtak.

App. Amount: - 38,000/-

Time Limit: 15 Days

Sr. No.	H.S.R / Ref. No	Description	Qty. / Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	13.30	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	33.50 Kg		
2.	13.28	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Angle:- 40*40*5 mm	51.400 Kg		
3.	13.18	Providing and fixing hard drawn steel wire fabric 75 mm X 25 mm rectangular mesh with 3.25 mm dia wire fixed on steel windows of standard rolled sections with 3 mm thick flat iron cover moulding of 12.5 mm width fixed with machine screws welded complete in all respect.	4.55 Sqm		
4.	11.77 + 11.78	Painting two coat with pink primer	6.825 Sqm		
5.	22.88.6	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 50 mm dia nominal bore	8.53 Mtr.		
6.	12.37.2	Providing and fixing ISI marked flush door shutters confirming (30mm)	1.36 Sqm		
7.	N.S.	P/F G.I elbow 2"	08 Nos.		
8.	N.S.	Cutting thread on G.I pipe by laith machine	08 Nos.		
9.	N.S.	Labour for fixing G.I pipe with CC 1:1½:3, ½" * ½" * ¾" i/c cutting of CC	08 Nos.		

## DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Misc. work at Gate No.04, Public Administration, Gymnasium, B.C.A, UIET and Law Department in MDU, Rohtak.

App. Amount: - 38,000/-

Time Limit: 15 Days

Sr. No.	H.S.R / Ref. No	Description	Qty. / Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	13.30	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	33.50 Kg		
2.	13.28	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Angle:- 40*40*5 mm	51.400 Kg		
3.	13.18	Providing and fixing hard drawn steel wire fabric 75 mm X 25 mm rectangular mesh with 3.25 mm dia wire fixed on steel windows of standard rolled sections with 3 mm thick flat iron cover moulding of 12.5 mm width fixed with machine screws welded complete in all respect.	4.55 Sqm		
4.	11.77 + 11.78	Painting two coat with pink primer	6.825 Sqm		
5.	22.88.6	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 50 mm dia nominal bore	8.53 Mtr.		
6.	12.37.2	Providing and fixing ISI marked flush door shutters confirming (30mm)	1.36 Sqm		
7.	N.S.	P/F G.I elbow 2"	08 Nos.		
8.	N.S.	Cutting thread on G.I pipe by laith machine	08 Nos.		
9.	N.S.	Labour for fixing G.I pipe with CC 1:1½:3, ½" * ½" * ¾" i/c cutting of CC	08 Nos.		

10.	12.7.2.1	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. 2. Kiln seasoned and chemically treated Hollock wood. 1. 35 mm thick shutters	3.17 Sqm		
11.	12.9.6.1	P/F Coir Veneer Board (conforming to IS 14842) 1. 12 mm thick	1.79 Sqm		
12.	13.3	Providing and fixing pressed steel door frames	4.70 Mtr.		
13.	12.159.2	P/F glazing in aluminum door, window and ventilator shutters.	1.61 Sqm		
14.	12.98.1	Providing and fixing aluminium sliding door bolts. Size:- 300x16 mm	02 Nos.		
15.	12.98.2	Providing and fixing aluminium sliding door bolts. Size:- 250x16 mm	01 No.		
16.	12.99.4	Providing and fixing aluminium tower bolts. Size:- 150x10 mm	03 Nos.		

**Note:-**

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

*ASL*  
29/1/22

## DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Providing and fixing vitrified floor tiles in Lab No.213 UIET (E.E) in MDU, Rohtak.

App. Amount: - 12,500/-

Time Limit: 15 Days

Sr. No.	H.S.R / Ref. No	Description	Qty. / Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	5.43.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material etc. completed	10.40 Sqm		
2.	5.70	Disposal of building rubbish / malba / similar unserviceable dismantled or waste material	0.26 M3		
3.	10.63.2	P/L vitrified floor tiles	10.40 Sqm		

**Note:-**

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

*MN*  
29/12/20

## DETAILED NOTICE INVITING QUOTATIONS

Name of the work: - Supply of P.H items for Department of Pharmacy (New Building) in MDU, Rohtak.

App. Amount: - 28,034/-  
Time Limit: 07 Days

Sr. No.	H.S.R / Ref. No	Description	Qty. / Unit	Rate to be quoted by the bidder exclusive of GST, but including all other taxes, if any	Amount
1.	N.S.	PVC water tank	1500 Ltr. (02 No.)		
2.	N.S.	CPVC brass M.T 1½" (Supreme)	01 No.		
3.	N.S.	CPVC brass M.T 1"x1" (Supreme)	01 No.		
4.	N.S.	CPVC plain Tee 1½" x 1½" (Supreme)	02 No.		
5.	N.S.	CPVC plain union 1½" (Supreme)	03 No.		
6.	N.S.	CPVC tanki nipple 1½" (Supreme)	04 No.		
7.	N.S.	CPVC tanki nipple 1" (Supreme)	01 No.		
8.	N.S.	CPVC union 1" x 1" (Supreme)	01 No.		
9.	N.S.	CPVC ball valve 1" (Supreme)	02 No.		
10.	N.S.	CPVC pipe 1" (Supreme)	10' Rft.		
11.	N.S.	CPVC pipe 1½" (Supreme)	30' Rft.		
12.	N.S.	CPVC elbow 1" (Supreme)	04 No.		
13.	N.S.	CPVC solvent	100 g		
14.	N.S.	G.I socket 1½"	01 No.		
15.	N.S.	G.I reducer socket 1" x ¾"	02 No.		
16.	N.S.	CPVC ball valve 1½" (Supreme)	01 No.		

**Note:-**

In case of any difference in the unit & nomenclature if any of the HSR items of civil, PH work depicted in this DNIT and that given in HSR, the unit and nomenclature given in HSR shall be applicable.

*[Handwritten Signature]*  
29/4/20